

7- 34-41W

Company- PANHANDLE EASTERN PIPE LINE COMPANY
 Farm- Wacker No. 1

SEC. 7 T. 34 R. 41W
 C SE/4

County Morton

KANSAS

Total Depth. 5288'


Comm. 8-9-56

Comp. 10-2-56

Shot or Treated.

Contractor. Holm Drilling Company

Issued. 12-1-56



CASING:

8 5/8" @1467' w/800 sx cem.

5 1/2" @4533' w/800 sx cem.

Elevation. 3432.5'

Production. open flow, After

Acid: 24,225 MCF

Rock Pressure: 430#

Figures indicate Bottom of Formations.

clay & sand	100
rock & shells	155
shale, shells & Gyp	960
sand	980
shale & shells	1240
Gyp & shells	1290
shale & shells	1380
Anhydrite & Gyp	1400
shale, lime & shells	1471
shale, lime & shells	2440
shale & lime	4700
shale & shells	4755
shale & lime	4870
shale & Sand	4911
lime & shale	5008
sand & shale	5080
lime & shale	5288

Total Depth

WELL TREATMENT RECORD

Acidized on 9/11/56 w/1000 gal 15% acid;
 Acidized 9/12/56 w/3000 gal 15% acid;
 Acidized on 9/13/56 w/1000 gal 15% acid;
 Flushed w/2500 gal dist & 200 gal wtr;
 Acidized on 9/17/56 w/1000 gal 15% acid;
 Acidized 9/18/56 w/1000 gal 15% acid
 Acidized on 9/20/56 w/1000 gal 15% acid
 Acidized 9/21/56 w/1000 gal 15% acid;
 Acidized on 9/22/56 w/5000 gal 15% acid;
 Acidized on 9/23/56 w/1000 gal 15% acid;

PERFORATIONS

4387'-4407'; 3800'-3812'; 3712'-3718';
 3725'-3737'; 3256'-3272'; 3198'-3208';
 Set Plug @3170' plugging these perfs.
 3108'-3112'; 3118'-3122' 3017'-3025'
 3041'-3045'; 3054'-3064'.

SCOUT TOPS

Waubansee	2756
Topeka	2978
Lansing	3475
Morrow	4572
Morrow Sand	4878
Keyes	5054
Mississippi	5070