

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


10-34-41W

Company- PANHANDLE EASTERN PIPE LINE CO.
Farm- Baughman No. 1-10

SEC. 10 T. 34 R. 41W
C NW SE

Total Depth. 2330'
Comm. 9-25-56 Comp. 9-30-56
Shot or Treated.
Contractor. Garvey Drlg. Co.
Issued. 4-20-57

County Morton
KANSAS



Elevation. 3403'

Production. 3500 MCF

CASING:

7" 570' w/250 sx cem.
4 1/2" 2326' w/300 sx cem.

Figures indicate Bottom of Formations.

sand-red bed 450
shale-red bed 500
shale-gyp rock 550
shale-shells 573
red bed-gyp 1025
sand-shale-anhydrite 1625
shale-shells 2085
shale-cherty lime 2330
Total Depth

TOPS:

Krider 2169
Winfield 2230

Perf. 2262-2263'; 2271-2273'; 2230-2235';
2240-2243'; 2246-2252'; 2170-2180';
2186-2203'.

Acidized on 10-4-56 w/1000 gal.
" " 10-5-56 w/3000 gal.
" " 10-6-56 w/1000 gal.
" " 10-8-56 w/1000 gal.
" " 10-9-56 w/3000 gal.