

11-34-41W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,


Wichita, Kansas

Company- CITIES SERVICE OIL CO.
Farm- Eagley "A" No. 1

SEC. 11 T. 34 R. 41W
NW NW SE
225' S & E of Center

Total Depth. 2340
Comm. 1-29-52 Comp. 2-3-52
Shot or Treated.
Contractor. Barbour Drllg Co.
Issued. 11-22-52

County Morton
KANSAS



CASING:

8 5/8" 305' CL cem w/200 sx., circ.
5 1/2" 2339' cem w/500 sx.

Elevation. 3385
~~3386 (rod)~~
Production. 2,700,000 gas

Figures Indicate Bottom of Formations.

sand, clay	65
sand, shells, redbed	285
red bed	489
anhydrite, gyp	500
shale	705
shale, gyp	750
shale, sand	900
anhydrite	950
shale, anhydrite	1017
anhydrite	1060
shale, shells	1480
shale, lime	1815
shale	1885
shale, lime	2330
Total Depth Rotary table	
Circ. waiting on	
Halliburton unit.	
shale	2340
Total Depth	
Tops: Scout.	
Herrington	2186
Upper Krider	2221
Lower Krider	2236
Winfield	2280

Run Halliburton log.