


15-34-41W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - Commissioners "B" No. 1

SEC. 15 T. 34 R. 41W
SW SW SW NE
100' N & 100' E.
of center
County. Morton

KANSAS



Total Depth. 2430 RTD=2426 corr. to ground
Comm. 7-16-49 Comp. 7-24-49
Shot or Treated.
Contractor. Holm-Louis Drlg. Co.
Issued. 7-7-51

CASING:
8 5/8" 640' cem w/300 sxs.
5 1/2" 2380' cem w/900 sxs.

Elevation. 3434

Production. 9,970,000 gas

Figures Indicate Bottom of Formations.

sand, shale	200
chalk, shale	290
red bed	345
red bed, shells	525
lime	555
shale, shells	620
red bed	940
lime	1000
lime, shale	1050
lime	1080
shale, shells	1465
lime, shale	1530
lime	1590
lime, shale	1785
broken lime	1835
shale, shells	1850
shells, shale	1865
lime, shale	1985
shale, shells	2015
lime	2070
shale, shells	2115
lime, shale	2300
shale, shells	2381
lime, shale	2430 RTD
Total depth 2430=2426	Corr. to ground

Ran Schlumberger Elec. log.

Tops:

Herington	2217
Krider	2254
Winfield	2304
Fort Riley	2358

Perforated:

30 shots	2244-50
90 shots	2256-74
20 shots	2284-88
30 shots	2304-10
20 shots	2312-16
30 shots	2318-24
30 shots	2334-40