

19-34-44W  
41W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- PANHANDLE EASTERN PIPE LIME CO.  
Farm- Tucker No. 1

SEC. 19 T. 34 R. 41W  
C SW NE  
1980' W EL 1980' S NL

Total Depth. 5250'  
Comm. 6-12-57 Comp. 6-4-57  
Shot or Treated.  
Contractor. Barvey Drlg. Co.  
Issued. 10-5-57

County Morton  
KANSAS



Elevation. 3466'

Production. Swb. & flowed 10 BOPH

Figures indicate Bottom of Formations.

surface clay-sand	165
sdv shale-shells	300
red bed-shells	795
red bed-gyp-sand	1070
sdv shale-shells	1370
red bed-shale shells	1410
Anhydrite	1458
shale-shells	1477
Anhydrite	1500
shale-shells	1960
shale-shells w/sand	
strks	2070
lime-shale	2167
shale-sand-lime	2240
shale-lime	3090
lime	3570
lime-shale	3785
lime	3870
lime-shale	4414
shale	4485
shale-lime	4741
shale	4920
lime-shale	5149
lime	5250
Total Depth	

Producing Formation:  
159 B OPD/ Upper Morrow  
30 BOPD / Cherokee

Perforation:  
4674' - 4686' ; 4397' - 4408'

Well Treatment Record:  
Acidized w/1000 gals 15% acid on  
6-23-57

TOPS:	
Krider	2093
Winfield	2177
L. Council Grove	2559
Wabaunsee	2782
Topeka	3002
Greenwood-Lansing	3280
Lansing	3511
Cherokee	4272
Cherokee sand	4397-4418
Morrow shale	4592
Vorrow sand	4674-4685
Morrow "Keyes" Sand	5085-5102
Morrow "Keyes" Sand	5119-5131
Mississippian	5187