

Company- Panhandle Eastern Pipe Line Company
Farm-Tucker No. 02

19-34-41W
SEC. 19 T. 34 R. 41W

C SE NE
3300' N fr. S.L. & 4580'
E fr. W.L. NE/4
County Morton KANSAS

Total Depth. 5236'

Comm. 8-17-57

Comp. 9-30-57

Shot or Treated.

Contractor. Garvey Drilling Company,

Issued. 12-21-57

CASING:

8" @ 1527'

5" @ 4800'

Elevation. 3454' GL.

Production. 46 BOPD.

Figures indicate Bottom of Formations.

sand & clay	150
shale, shells & red bed	445
red bed & shells	835
Gypsum	875
shale & shells	950
red bed, Gypsum & shells	1010
sand	1175
lime, red bed, Gypsum & shells	1207
shale & shells	1490
red bed & shells	1530
shale & shells	2065
shale	2335
shale & shells	2615
lime & shale	4415
sand & shale	4436
lime & shale	4441
lime	4462
lime w/chert strks.	4510
lime & shale	4697
sand	4735
shale & lime	5052
sand	5085
sand & shale	5118
lime & shale	5147
sand	5167
lime	5170
lime w/Chert strks. & Pyrite	5236
Total Depth.	

TOPS:

Wabaunsee	2796
Topeka	3017
Lansing	3527
Cherokee	4292
Cherokee Sand	4417
Morrow Shale	4615
Upper Morrow Sand	4717
Lower Morrow "G" Sand	5062
Lower Morrow "Keyes" Sand	5136
Mississippian	5201

Perforations:

4718-4721'