

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
 508 East Murdock,  
 Wichita, Kansas


31-34-41W

Company- ANADARKO PRODUCTION CO.  
 Farm- Nusser No. 1

SEC. 31 T. 34 R.41W  
 C SE NW

Total Depth. 3340'  
 Comm. 9-14-60 Comp. 9-29-60  
 Shot or Treated.  
 Contractor. Earl Wakefield  
 Issued. 12-17-60

County Morton  
 KANSAS



Elevation. 3481.09 GL

CASING:  
 8 5/8" 501' cem w/250 sx.  
 4 1/2" 3330' cem w/150 sx.

Production. 33,900,000 CFG

Figures Indicate Bottom of Formations.

shale & shells	250
red bed	505
red bed & shale	980
red bed	1130
sand	1280
shale & shells	1465
red bed & shale	1495
shale & lime	1660
lime & shale	1825
shale & lime	2110
lime & shale	2235
shale & lime	2400
shale	2530
lime	2605
shale & lime	2715
lime	2835
lime & shale	3025
chert & lime	3097
lime	3165
lime & shale	3250
lime	3340
Total Depth	

TOPS: SCOUT

Wabaunsee	2829
Topeka	3044
Greenwood Lansing	3316

OIL OR GAS SANDS OR ZONES - PERFORATIONS ACIDIZING & FRACTURING INFORMATION

Name	From	To	No. of Shots	Gallons Used	Kind Used
Topeka	3174	84	20	3000	15%
	3120	26	12	15000	10%
	3098	3103	10		