

PANHANDLE EASTERN PIPE LINE COMPANY

Tucker 01
C SW NE
Section 19-34S-41W
Morton County, Kansas

Formation Tops

| | |
|--------------------|-------|
| Marmaton | 4181' |
| Cherokee | 4272' |
| Morrowan Shale | 4592' |
| "C" Ss. | 4674' |
| Lower Morrowan Ss. | 5010' |
| Lower Morrowan Ss. | 5084' |
| Lower Morrowan Ss. | 5119' |
| Mississippian | 5187' |
| Total Depth | 5250' |

Completion Information

Spud May 12, 1957.
Set 1492' of 8 5/8" casing with 800 sacks cement.
Set 4780' of 5 1/2" casing with 500 sacks cement.
Cleaned out to 4722'.
Perforated 40 holes 4674-4684'.
Swabbed 14 BO in 12 hours.
Set plug at 4450'.
Perforated 44 holes 4397-4408'.
Acid 1000 gallons. 35 BOPH.
Drove plug; ran tubing with dual completion packer at 4613'.
Pulled tubing and packer; set packer at 4370' and squeezed Cherokee (4397-4408) with 200 sacks cement.
Drilled plug and ran tubing.

Completion Test: August 20, 1957.
Pumped 159 BOPD from the
Morrowan "C" Ss. 4674-84'.