

PANHANDLE EASTERN PIPE LINE COMPANY

Tucker 02
C SE NE
Section 19-34-41
Morton County, Kansas

Formation Tops

Marmaton	4206'
Cherokee	4292'
Atokan	4539'
Morrowan Shale	4615'
"C" Ss.	4717'
Lower Morrowan Ss.	5062'
Lower Morrowan Ss.	5136'
Lower Morrowan Ss.	5166'
Mississippian	5201'
Total Depth	5236'

Completion Information

Spud August 17, 1957.
Set 1527' of 8 5/8" casing with 700 sacks cement.
Set 4800' of 5 1/2" casing with 300 sacks cement.
Cleaned out to 4768'.
Perforated 12 holes 4718-4721'.
Tested 27 gallons OPH. Treated with 100 gallons
mud acid, 1000 gallons lease oil, no sand.
Fractured 3000 gallons lease oil and 1500# sand.
Swabbed 145 bbls. oil and 50 bbls. salt water in 17 hours.

Completion Test: Waiting on test.