

PANHANDLE EASTERN PIPE LINE COMPANY

Wacker 1-7
C of SE
Section 7-34S-41W
Morton County, Kansas

Formation Tops

Marmaton	4156'
Cherokee	4244'
Atokan	4462'
Morrowan Shale	4572'
"F" Ss.	4878'
"G" Ss.	4992'
Keyes Ss.	5054'
Mississippian	5070'
Total Depth	5287'

Completion Information

Spud August 9, 1956.
Set 1465' of 8 5/8" casing with 800 sacks cement.
Set 4533' of 5½" casing with 800 sacks cement.
Cleaned out to 4579'.
Perforated 100 holes 4387-4407'.
Acid 5000 gallons; flush 2500 gallons distillate
and 2000 gallons water.
Swab 3 gallons oil and 8 gallons water with 280 MCF.

Completion test: Completed in Greenwood Reservoir.