

MAP NO. _____ 1-17-61 ELEV. 3441DF, 3443KB
STATE Kansas COUNTY Morton SEC. 28 Twp 34S Rge 41W
OPERATOR Cities Service Petroleum Co. * LOC. C NW SE
WELL NO. 3 FARM NAME Webb "A" FT. FROM _____ LINE _____
OL Wilburton FT. FROM _____ LINE _____
FR. 11-11-60 SPUD 11-11-60 COMP. 1-13-61

CONT./GEOL. Lohman & Johnson Tools

NAME PRODUCING INTERVAL FROM — TO PERF. W/HOLES TREATMENT RECORD
a Topeka 3096-3154 66 17,500 Ac

b _____

c _____

d _____

d I. P. OIL/DIST. _____ WTR. COF GAS 3000 M.C.F.P.D. _____ CHK. _____ HRS. 24

b " " " " " "

c " " " " " "

d _____

D & A ()

SIP# 383.5 FI TP # _____ FI CP# _____ SIBHP _____

GOR. _____ GR. _____ PBDT 3168 TD 5225

SIZE	DEPTH	CASING - CEMENT RECORD W/SAX.	SIZE	DEPTH	W/SAX.
<u>8 5/8"</u>	<u>1459</u>	<u>675</u>			
<u>5 1/2"</u>	<u>5060</u>	<u>500</u>			

OPERATOR Cities Service Petr. WELL NO. #3 Webb "A" ELEV. 3441 DF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
			Topeka	3096	
			Heebner	3486	
			Toronto	3502	
			Lansing	3656	
			Marmaton	3912	
			Morrow	4750 - 1307	
			Morrow Sand	4886-4930	
			Morrow Sand	4952-80	
			Morrow Sand	5014-21	
			Morrow Sand	5198-5219	

* Formerly Cities Service Oil Company.

Spud 11-11-60, 8 5/8" @ 1459 w/675 sx.

DST #1 (Morrow) 4890-4918, op 1 hr, GTS 9 mins, Ga 180 MCF/25 mins, TSTM/35 mins, Rc 1530' gassy oil + 900' SW, FP 405-1060, SIP 1475/20 mins.

DST #2 (Morrow) 4958-93, op 1 hr, GTS 2 mins, Ga 1060 MCF/60 mins, Rc 5' GCM, FP 105-125, SIP 1470/20 mins.

RTD 5225, Ran logs (Sj), 5 1/2" @ 5060 w/500 sx. MICT. CO to 5002.

FP/32/4896-4902, Swb 2 1/2 BO/10 hrs, SQ 4896-4902 w/cem. CO to 4898.

2807 280W

p 28/4887-94, 500 Ac, swb ld & swb 5 BFPH (95% wtr), SQ/4887-94 w/100 sx. CO.

P 40/4890-4900, 1000 MA, rec ld, swb 30 BFPH/4 hrs (95% wtr & 5% oii). Set BP @ 3270.

Shawnee A → p 16/3240-44, 500 Ac, rec ld, swb 8 BWPH, set BP 3200. p 20/3181-86, 500 Ac, swb ld/SSG & wtr, SQ/3181-86 w/125 sx. CO to 3168.

p 10/3149-54, g 1,746 MCF, 1000 MA, SWB ld, g 2,800 MCF/15 hrs, p 16/3096-3100, p 40/3132-42, g 3,284 MCF, 3000 Ac, Swb ld, g 2,537 MCF + 4 GWPH/17 hrs, 1500-5% Ac, g 2,860 MCF + 3 GWPH. 12,000 15% Ac, rec ld, g 3,500 MCF + 2 GLWPH, 24 hr BD g 3,360 MCF (dry).

IF COF = 3,000 MCF, SIP 383.5, from Topeka (3096-3154).

Should be part of 3132-52