


***** OFFSET
 State Ks Field TOLOGA N.E.
 Company PEPL County MORTON
 Farm TUCKER No. 0-2
 Sec. 19 Twp. 34 Range 41
 Spot SE NE
 Contractor Garvey
 Remarks 5200' MISS

Comm. 8-17-57 Comp. 10-23-57
 Elev. DF 3461 GL 3456 KB TD 5236 PB 4750
 Pay Mar 4718-21



I.P. PUMP 46 BOPD Press. G. RAY. 37.5"
 Casing Record: 13 3/8 7"
 20" 10 3/4 5 1/2" 4000/200
 16" 8 5/8 1527/700

	Sample	Log
WOC		Walt 2796
AUG 28 TD 3878 shut		TOP 3017
down for repairs		CSO LANS 3297
SEP 4 4415-23 rec		LANS 3527
6' ls & sd 4423-36		CHER 4292
rec 11' ls, chert & sd		MOR 4615
SEP 11 DST 4398-4436		" sd 4717-36
op 2 hr. rec 180'		" " 4965-73
SGCM FP 70-90		" G' sd 5062-91
BHP 295/20		W/KEYS 5138-50
44697-4723 rec		4" 5166-85
24'; 18' sh, 6' sd sh		MISS 5201
for stain & odor		
44723-35 rec 11 1/2'		
9 1/2' sd stain & odor		
2' sd title		

DST 4719-35 op 1 1/2 hr. GTS 35"
 + STM rec. 280' GCO + 2265' 300 GCSW
 180' H08 GCM FP 240-966 BHP 1040/20
 DST 4958-81 op 20" rec 10' M
 FP 0 BHP 569/20 ~~45100 pump to~~
 SEP 18 DST 5064-5100 op 30" rec. 10' M
 FP 0 BHP 890/20

DST 5151-70 op 1 hr. rec. 120' MSW
+ 860' SW FP 130-450 BHP 1170/20"

RTD 5236 ran log ~~5 1/2~~ MIST

SEP 25 RUCT CO 4768 G/R pf 6/4720

swab 7 gal OPH FR/3000 Sd/2000

swab 80 B load oil & Dslg M ran T @ 2820 ^{8 pk}

~~19/200~~ cement

OCT 2 CO 4750 swab re-pf 12/4718-21

swab 27 gal OPH no wti ran T & PK


MA/100 FR/4000 Sd/1500 swab 145 B0 +

50 BSW/17 hr. Pulled T & PK ran T & rods

to 4716 POP

OCT 9 3 OCT 16 OCT 20 ✓ CEF pump 46 BOPD

+69 BXWPD ~~69 BSW~~ GRAV. 37.5



AMARILLO TOPS

3456 GL

Topeka 3019 (+437)

Heebner 3382 (+74)

Lansing 3510 (-54)

Cherokee 4290 (-834) tst'd Sg

Morrow 4629 (-1173)

"L" Sd 4716 (-1260) T 20', por 18', C 46 B0 + 69 BXWPD

"S-3" Sd 4963 (-1507) T 11', por 2', NS

"S-3" Sd 4996 (-1540) T 14', por 0', NT

"S-3" Sd 5062 (-1606) T 29', por 4', NS

Keyes 5136 (-1680) T 20', por 17', XW

Keyes 5166 (-1710) T 21', por 20', XW

Chester 5187 (-1731)

TD 5236 (-1780)