



DST #2 (Morrow) 4968-83, op 1 hr, rec 449' oil + 914' O&XW + 2080' XW, FP 895-1565, SIP 1575/20 mins.

Core #4 4984-5000, rec 16' sd & sh.

RTD 5340, Elogs to 5340. 5½" @ 5181/300 sx. MICT, CO to 5140.

P 40/5116-26, 16 hr g 18,100 MCF (gas well already in section), set BP @ 4960.

P 40/4908-18, f 22.24 BOPH/3 hrs, ½" ck, ran 2" T to 4934. Swb 82 BO/7 hrs, FCP 200#.

IP swb & flo 240 BOPD, 2" T, gty est 40°, FCP 200, FTP 80, from Morrow (4908-18).

LIBERAL TOPS

3509 K.B.

Topeka 3160 (+349)

Heebner 3548 (-40)

Toronto 3566 (-57)

Lansing 3704 (-195)

Marmaton 3986 (-477)

Morrow 4808 (-1299)

"L" Sand 4898 (-1389) 26/28

U/"L" Sand 4968 (-1459) 44/44

L/"L" Sand 5060 (-1551) 12/14

"L" Sand 5116 (-1607) 18/22

"S-3" 5266 (-1757) 7/16

"S-3" 5290 (-1781) 18/25

5340 TD

*State tech*

*3/15/61*

*43.84 BO/8'*

*132 BO/24'*

*GOR 1000:1*