

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,

Wichita, Kansas

32-34-42W

Company. COLORADO OIL & GAS CORPORATION
Farm. Central Life No. 1

SEC. 32 T. 34 R. 42W
C NW/4

Total Depth. 4730

Comm. 10-8-55

Comp. 10-31-55


Shot or Treated.

Contractor. Holm Drilling Co.

Issued. 1-21-56

County Morton

KANSAS



Elevation. 3532 GL

Production. 5,200,000 CFGPD

Figures Indicate Bottom of Formations.

surface clay	42
surface clay & sand	520
shale & shells	740
gyp	895
shale & gyp streaks	1205
shale & shells	1313
anhydrite	1320
shale & shells	2358
shale & lime	4614
shale & sand	4636
lime & shale	4730
Total Depth	

SCOUT TOPS:

Wabaunsee	2639
Elmont	2868
Topeka	2949
Lecompton	3069
Lansing	3263
Marmaton	3835
Morrow	4193
Keyes	4620
Mississippi	4660

Ran Schlumberger Electric Log.

DST #1: 3557-97 w/ 40' anchor final meas.
196 MCF, rec. 180' GCM.

DST #2: rec. 990' muddy & SW.

DST #3

DST #4: rec. 140' drlg. mud, IFP 80#,
FFP 150#, BHP 590#

DST #5: 3975, rec. 1400' muddy SW

DST #6:

DST #7: 4614-22, open 1 hr, closed 1
hr, SIP 1½ hrs. drld to 4430-drld to 4632-
drld to 4636