

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

2. 34. 42W

Company-PANHANDLE EASTERN PIPE LINE CO.
Farm- Hill No. 1SEC. 2 T. 34 R. 42W
SW-SW NE
2400' fr EL, 2840' fr SL

Total Depth. 3310

Comm. 4-3-55

Comp. 4-12-55


Shot or Treated. 6000 gals. 15% & 5000 gals 7½% acid

Contractor. Garvey Drilling Co.

Tested. 7-16-55

County Morton

KANSAS



CASING:

10 3/4 @ 528' w/ 350 sx cmt.

7 in. @ 3298' w/ 225 sx cmt.

Elevation. 3395.30

Production. 30,407,000 CFG
RP 425½

Figures indicate Bottom of Formations

surface soil & sand	50
sand & clay	200
red bed & sand	465
red bed & gyp	528
sand & red bed	600
red bed, gyp, anhydrite & sand streaks	890
red bed & sand	1125
red bed & shells	1485
red bed; shale & anhydrite	1922
red bed, shale, anhydrite stk.	2165
red bed & anhydrite streaks	2295
lime & shale	3310
Total Depth	

TOPS:

Wabaunsee	2656
Topeka	2888
Lansing	3147

Perf. (Sqzd. off) 3231-36, 3210-15,
3205-10; 3198-3201, 3191-96, 3184-88,
3152-57, 3160-70Perf. 3102-10; 3090-95, 3021-41,
2945-52, 2927, 32, 2913-17,

Well Treatment Record:

Acidized on 4-17-55 with 1000 gal of 15% acid.

"	"	4-19-55	"	2000	"	"	7½% acid.
"	"	4-19-55	"	1000	"	"	15% acid.
"	"	4-19-55	"	2000	"	"	"
"	"	4-20-55	"	3000	"	"	7½% "
"	"	4-20-55	"	2000	"	"	15% acid.