


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. PANHANDLE EASTERN PIPE LINE CO.
Farm. Interstate No. 1

6. 34. 72 W
SEC. 6 T. 34 R. 42W
C E/2 E/2 W/2 SW
1320' fr SL, 1280' fr WL

County Morton
KANSAS

Total Depth. 3110
Comm. 4-29-55 Comp. 5-26-55
Shot or Treated. 15,000 Gal. 15% acid
Contractor. Falcon Seaboard Drilling Co.
issued. 8-13-55



Elevation. 3461.71'

Production. 8,873,000 CFG
RP 412#

CASING:

10 3/4 @ 619' w/ 325 sx cmt.
7 in. @ 3110' w/ 300 sx cmt.

Figures indicate Bottom of Formations.

sand	70
red bed & sand	475
red bed, shells & sand	656
sand & red bed	821
red bed; lime & shells	1172
red bed, sand & lime	1407
red bed & sandy lime	1467
lime, sand & shale	1690
lime & red bed	1873
lime & shale	2117
shale, lime & sand	2241
sandy lime	2354
lime	2410
lime w/ broken shale	2502
lime & shale	2677
shale & broken lime	2761
sand, shale & lime	2825
lime & shale	2988
sandy lime	3058
lime & shale	3110
Total Depth	

TOPS:

Wabaunsee	2557
Topeka	2774
Lansing	3017

Perf. (squeezed) 3053-58, 3025-34,
2976-82

Perf. 2896-2916, 2859-64, 2835-46,
2804-19,