

14-34-42W
WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company. COLUMBIAN FUEL CORPORATION
Farm- Tucker No. 1

SEC. 14 T. 34 R. 42W
C SW/4

Total Depth. 5010

Comm. 1-1-56


Comp. 1-22-56

Shot or Treated.

Contractor. Midwestern Drillers, Inc.

Issued. 4-14-56

County Morton
KANSAS



Elevation. 3482 RB

Production. 17,125,000 CFGPD

CASING:

9 5/8 1343' w/ 650 sx cmt.
5 1/2 4950' w/ 470 sx cmt.

Figures indicate Bottom of Formations.

clay, sand & red bed	278
red bed, sand & gravel	649
red bed & anhydrite	1127
gypsum & anhydrite	1343
anhydrite & shale	1448
red bed, shale & shells	2035
anhydrite & shale	2250
lime & shale	2615
chalky lime & shale	2745
lime & shale	3169
lime	3245
lime & shale	3701
shale & shells	3750
lime & shale	4132
lime	4187
shale & sand	4197
lime & shale	4482
shale	4641
shale & sand	4700
lime & shale	4750
sandy lime & shale	4822
lime & shale	4855
shale & sand	4914
lime & shale	5010
Total Depth (RBM)	

SCOUT TOPS:

Topeka	2940
Lansing	3207
Purdy	4740
Keyes	4892
Chester	4914

DST #1 @ 3660
DST #2 @ 4197
DST #3 @ 4273
DST #4 @ 4750

Ran electric log to TD