

15-34-42W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. PANHANDLE EASTERN PIPE LINE CO.
Farm. Riley "B" No. 1

SEC. 15 T. 34 R. 42W
NW NW SE
2490' fr EL, 2440' fr SL

Total Depth. 3222
Comm. 4-23-55 Comp. 5-31-55
Shot or Treated. 11,000 gals. 15% acid
Contractor. Garvey Drilling Co.
Issued. 8-13-55

County Morton
KANSAS



CASING:

10 3/4 @ 600' w/ 350 sx cmt.
7 in. @ 3200' w/ 300 sx cmt.

Elevation. 3472.48'

Production. 38,448,000 CFG
RP 412#

Figures indicate Bottom of Formations

surface sand & soil	40
sand	100
sand & clay	270
red bed; gyp & sand	654
red bed, sand & anhydrite	910
sand & red bed	1090
red bed; sand & anhydrite	1335
red bed, sand & shale	1545
red bed & shale	1725
red bed; shale & anhydrite	2092
red bed, shale & lime	2276
shale & lime	3015
lime	3222
Total Depth	

TOPS:

Wabaunsee	2643
Topeka	2863
Lansing	3114

Perf. (squeezed) 3134-40; 3124-34
Perf. 2980-92, 2996-3010, 3028-34,
3043-49; 3056-71, 2946-52, 2923-33,
2907-13, 2893-97.