

21-34-42W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PANHANDLE EASTERN PIPE LINE CO.
Farm- Kansas No. 1

SEC. 21 T. 34 R. 42W
CE/2 E/2 E/2 NW
2490' fr EL, 1320' fr NL

Total Depth. 3077
Comm. 5-29-55 Comp. 6-16-55
Shot or Treated. 19,000 gals 15% acid
Contractor. Falcon-Seaboard Drilling Co.
Issued. 10-15-55

County Morton
KANSAS



10 3/4" CASING: 589' w/ 300 sx cmt.
7 in. 3067' w/ 300 sx cmt.

Elevation. 3483.48

Production. 24,404,000 CFGPD
RP 420#

Figures Indicate Bottom of Formations.

red bed & sand	650
sand & lime	1095
red bed & sandy lime	1270
shale & lime	1532
red bed & lime	1744
lime & shale	2782
sandy lime & shale	2840
lime & shale	3077
Total Depth	

TOPS:
Wabaunsee 2493
Topeka 2694
Lansing 2927

Perf.: 3004-14, 2993-99, 2983-88,
2965-75; 2930-50; 2916-21, 2887-93,
2852-59, 2841-47, 2827-34,