

23. 34-42u


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- CITIES SERVICE GAS DEV. CO.
Farm- Bradshaw "B" No. 1

SEC. 23 T. 34 R. 42W
NE NE SW
330' S 330' W of C SW

Total Depth. 3240' PB 3150'
Comm. 10-10-55 Comp. 11-16-55
Shot or Treated.
Contractor. Holm Drlg. Co.
Issued. 4-20-57

County Morton
KANSAS



Elevation. 3481' DF.

Production. 14,400 MCF

Figures indicate Bottom of Formations.

CASING:
8 5/8" 600' w/200 sx cem.
5 1/2" 3233' w/300 sx cem.

Log Tops by Co.

Topeka 2928
Lansing 3184

RTD 3240, ran log, MICT, perf 25/3181-96,
ns, A/2000, flush 3200/wtr., swb
down, sho gas 40 gal wtr/hr;
set plu @ 3150, perf 40/3114-22, A/1000,
wtr/3200, swbd 4 hrs., g 2,120 MCF 4
3 qts. WPH, 9 hrs., g 1,750 MCF 4 1 1/2 qts.
WPH, 18 hrs. 1,340 MCF 4 1 1/2 pts. PH, 20
hrs. 1,340 MCF 4 1 1/2 pts WPH;

Set Baker plug @ 3100, perf 210/3038-80,
A/5000, wtr/3175, swbd dry 1 1/2 hr. g 6,400
MCF, 24 hrs. BD g 6,4000 MCF 4 mist;

Set Baker plug : 3020, perf 75/2995-80,
120/2976-52, 40/2936-28, A/5000, wtr/3000,
swbd, g 1 1/2 hrs. 7,830 MCF, 14 hrs. blow
6,400 MCF w/hvy mist, A/a000 7 1/2%, wtr/3000,
Ø plug @ 3020 & 3100, swbd down, 12 hr ED g
7,150 MCF;

SI 72 hrs., blow 12 hr. to dry, 5 min, g
20,700 MCF, 10 min g 17,100 MCF, 15 min
g 14,400 MCF, 20 min g 13,700 MCF, SIP
427#;

72/20 14,400 MCF, SIP 427#.

Pay Zones: 2928-36; 2952-76; 2980-95;
3114-22