

23-34-42W *And P.*

WELL LOG X

COMPANY CITIES SERVICE OIL & GAS CORPORATION

SEC. 23-34-42W

FARM Bradshaw "C" NO. 3

LOC. 1650' FSL & 4620' FEL


TOTAL DEPTH 4950'

COUNTY Morton, Ks.

COMM. 2-04-85

COMP. 2-14-85

CONTRACTOR ZENITH DRILLING CORPORATION



CASING 1385' of 8 5/8", 24# casing, cemented with 650 sacks cement

ELEVATION

PRODUCTION

APR - 3 1985

FIGURES INDICATE BOTTOM OF FORMATIONS

*State Geological Survey
WICHITA BRANCH*

40	Sand
225	Sand and Red Bed
800	Red Bed and Anhydrite
1379	Anhydrite and Sand
1680	Sand and Shale
2190	Red Bed and Anhydrite
2620	Sand and Shale
2980	Lime and Shale
3170	Dolomite
4950	Lime and Shale

75 sq. cement plug 4950-4800' Keyes
50 " " " 4750-4650' Morrow
50 " " " 4500-4400' Morrow

RECEIVED
STATE CORPORATION COMMISSION

MAR 18 1985

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING INFORMATION

1st Plug	100 sacks cement at 3150' - 2922'
2nd Plug	50 sacks cement at 1428' - 1328'
3rd Plug	50 sacks cement at 690' - 590'
4th Plug	10 sacks cement at 40' - 4'

5 sacks cement in rat hole
5 sacks cement in mouse hole

Job complete 11:00 A.M. 2-14-85

State of KANSAS }
 County of SEDGWICK } SS