

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock,

Wichita, Kansas


26. 34. 424

Company- PANHANDLE EASTERN PIPE LINE
Farm- Riley "C" No. 01

SEC. 26 T. 34 R. 42W
C SW

Total Depth. 4620'
Comm. 6-7-56 Comp. 6-26-56
Shot or Treated.
Contractor. Garvey Drlg. Co.
Issued. 1-12-57

County Morton
KANSAS



CASING:
8 5/8" 1497' w/800 sx cem.
5 1/2" 4575' w/800 sx cem.
2" tbg. 4489'

Elevation. 3501.93'

Production. State Test 42 BOPD

Figures indicate Bottom of Formations.

surface clay-sand	180
sand-red bed-rock-gyp	675
red bed-shale	812
Anhydrite	855
gyp-red bed	920
red bed-sand	1070
sand-rock	1115
shale-red bed	1235
shale-gyp	1335
shale-shells	1485
Anhydrite	1502
shale-sand-gyp	1870
shale-shells	2432
shale-anhydrite	2585
shale-lime	2868
lime	3315
lime-shale	3416
lime	3773
lime-shale	3831
lime	4154
lime-shale	4448
sand-shale	4604
lime	4620
Total Depth	

TOPS:

Wabaunsee	2534
Topeka	2732
CSO Lansing	2970
Lansing	3156
Cherokee	3894
Marmaton	4141
Morrow (scout)	4174
Purdy sand	4191
"G" sand (scout)	4478
Keyes sand (scout)	4563
Mississippi "	4593

PERFORATIONS:
4523-2533
4502-4516
2903-2980

WELL TREATMENT RECORD:
26,000 gals 15% acid &
5000 gals. jetra frac.