

WELL BEING RE COMPLETED AT PRESENT.

34-34-42W

COMPLETION REPORT
Central Life #1-34

LOCATION: C SW/4, Sec. 34-T34S-R42W, Taloga Field, Morton County, Kansas.

STAKED: July 9, 1955.

ELEVATION: 3534 GL, 3542 DF (L&S).

SPUD: 7 AM, July 15, 1955. Rotary-Holm Drilling Co., 7-15-55 to 9-1-55.
Cable Tools-Turpin Drilling Co., 9-2-55 to 9-11-55.

INTERMEDIATE CASING: 9-5/8", 36#, J55 set at 2211' GL w/600 sx. Circulated.

PRODUCTION CASING: 5-1/2", 14#, J55 set at 4812' GL w/600 sx. Top Cement 4210.

TOTAL DEPTH: 5519 RTD, 4698 FETD.

CORFS: None.

DRILL STEM TESTS: #1, 2656-99; #2, 2930-61; #3, 2966-93; #4, 3081-96;
#5, 3096-3130; #6, 3340-50; #7, 3362-80; #8, 3446-88;
#9, 3523-80; #10, 3590-3662; #11, 3680-3756; #12, 3969-81;
#13, 3990-4045; #14, 4311-30; #15, 4331-44; #16, 4432-41;
#17, 4472-82; #18, 4512-22; #19, 4568-88; #20, 4730-44;
#21, 5435-72; #22, 5476-5519.

FORMATION TOPS: Morrow Sand 4315 (-781)
Keyes 4424 (-890)
St. Louis 4725 (-1191)

PERFORATIONS:

<u>Zone</u>	<u>Formation</u>	<u>Made</u>	<u>Acid</u>	<u>Sq or Open</u>
4725-33	St. Louis	165 gal s.w./hr. w/scum B.S.	300 gal. MA-	Squeezed
4466-4505	Keyes	39,700 M nat. dry	1000 15%	Open
4428-32			3000 MA	Open

TUBING: None

DRILLING COMPLETE: September 11, 1955.

TESTS: Original Open Flow: 82,000 MCF
Original Rock Pressure:
Original Deliverability: 20,702 MCF

WELL CONDITION:

PIPE LINE CONNECTION: 2-27-56.

Orig. & 3: Mr. J. R. Coleman
4th cc: Mr. Don G. Benson
5th cc: Mr. D. W. Narden
7& 6th cc: Completion File
8th cc: Well File