

35. 34 - 42 W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PANHANDLE EASTERN PIPELINE CO.
Farm- Riley No. 3

SEC. 35 T. 34 R. 42W
C SE SW
3000' N of SL, 1980'
E of WL

Total Depth. 4675'
Comm. 10-10-58 Comp. 10-30-58
Shot or Treated.
Contractor. Holm Drlg.
Issued. 3-14-59

County Morton
KANSAS



CASING:
13 3/8" 425' cem w/400 sx.
8 5/8" 1425' cem w/100 sx.
5 1/2" 4630' cem w/300 sx.

Elevation. 3510' GL

Production. 87 BOPD

Figures Indicate Bottom of Formations.

surface sand	400
red bed	452
drilling dry	635
red bed & shells	850
shale & anhydrite	1060
shale, shells, anhy.	1427
red bed	1840
shale & shells	2055
shale & lime	4407
shale & sand	4442
shale	4505
sand & shale	4571
shale & lime	4675
Total Depth	

TOPS:

Topeka	2861
Lansing	3304
Cherokee	3936
Morrow Shale	4157
Morrow "F" Sand	4401
Morrow "G" Sand	4502
Morrow Sand	4518
Morrow Sand	4551
Keyes Sand	4580
Mississippian	4604

Morrow Sand 4526-4548', 88 shots, 1000 gals.
acid, 15%.