

35. 34. 42W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- PANHANDLE EASTERN PIPELINE CO.
Farm- Riley No. 4

SEC 35 T. 34 R. 42W
C NE NW
4625' to SL, 660' E
of SL

Total Depth. 4625'
Comm. 11-1-58 Comp. 11-14-58
Shot or Treated.
Contractor. Holm Drlg.
Issued. 3-14-59

County Morton
KANSAS



CASING:

8 5/8" 1433' cem w/800 sx.
5 1/2" 4624' cem w/175 sx.

Elevation. 3502' GL

Production. 49 BOPD

Figures indicate Bottom of Formations.

shale & sand	95
surface clay & sand	540
red bed & clay	800
shale & shells	2450
lime & shale	4625
Total Depth	

TOPS:

Wabaunsee	2662
Topeka	2860
Greenwood Lansing	3118
Lansing	3300
Cherokee	3934
Morrow Shale	4158
Morrow "F" Sand	4407 - 17
Morrow "F" Sand	4420 - 30
Morrow "G" Sand	4523 - 43
Morrow "G" Sand	4546 - 58
Keyes Sand	4589 - 4607
Mississippian	4620

Morrow "G" Sand 4529-4541' 48 shots
used 1500 gals & 500 gal. 15% & MGA.