

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,

Wichita, Kansas


35. 34. 42W

Company- PANHANDLE EASTERN PIPE LINE CO.
Farm- Watson No. 1

SEC. 35 T. 34 R. 42W
C SW/4

Total Depth. 4700'
Comm. 11-18-55 Comp. 12-12-55
Shot or Treated.
Contractor. Garvey Drlg. Co.
Issued. 6-16-56

County Morton
KANSAS



CASING:

8 5/8" 1506' cem w/600 sx
5 1/2" 4680' cem w/800 sx

Elevation. 3523' DE

Production. 101 BOPD

Figures indicate Bottom of Formations.

sand clay & red rock	225
red bed & gypsum	585
red rock, gypsum & sand	1370
red rock, anhydrite	1498
anhydrite	1520
red rock, shale, gypsum	1805
anhydrite, red rock	2040
red rock, shale	2143
red rock, sandy shale	2240
red rock, sandy lime	2398
lime	3475
sandy shale & lime	3538
shale & sand	3565
shale & lime	3905
lime	3953
shale & lime	4090
lime & shale streaks	4158
lime	4178
shale	4233
shale & sand	4330
shale & sand	4438
sand & shale	4460
shaley lime	4543
sandy lime	4553
shale & sand	4563
lime	4700
Total Depth	

Tops: Scout	
Waubensee	2659
Topeka	2853
1st Lansing	3166
2nd Lansing	3304
Morrow	3844
Cherokee	3937
Atoka	4088
Morrow Shale	4164
G. sand	4525
Keyes	4572