

35.34-42W

Company- PANHANDLE EASTERN PIPE LINE CO.
 Farm- Watson No. 01

SEC. 35 T. 34 R. 42W
 C SW $\frac{1}{4}$
 1320' N SL 1320' E WL SW

Total Depth. 4700'

Comm. 12-6-55

Comp. 12-10-55

Shot or Treated.


CORRECTED LOG.

Contractor. Garvey Drlg. Co.

Issued. 7-27-57

County Morton

KANSAS



Elevation. 3515.20' GL

Production. Swabbed 101 BOPD

CASING:

8 5/8" 1497' w/800 sx cem.
 5 1/2" 4680' w/800 sx cem.

Figures indicate Bottom of Formations.

sand-clay-red bed	225
red bed-gyp	585
sand-red bed-gyp	1370
red rock-anhydrite	1509
anhydrite	1520
red rock-shale-gyp	1805
anhydrite-red rock	2040
red bed-shale	2240
red rock-sdy shale-lime	2398
sdv shale-lime	4700
Total Depth	

TOPS:

Waubunsee	2659
**Topeka	2853
Greenwood Lansing	3116
Lansing	3304
Marmaton	3844
Cherokee	3937
Atoka	3088
Morrow sand	4164
*Morrow "G" sand	4525
Keyes	4575
Mississippi	4615

**Producing Formation - gas

* Producing Formation - Oil

Perforations:

1955-56 perf. 4587-4588'
 salt wtr., squeezed 4582-4583'
 " " " 4575-4578'
 " " , permanent plug @ 4565'.
 4527' - 4536'.

1957 perf.: 2862' - 2992'; 2922' -
 2830&; 2894' - 2902'.

Well Treatment Record;

1/4/56 - frac, w/500 gals.

Acidized 2/18-57 w/1000 gals.

" 3-20-57 w/2000 gals.

" 3-24-57 w/8000 gals.