

35-34-42W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- PANHANDLE EASTERN PIPE LINE CO.
Farm- Westerfield No. 01

SEC. 35 T. 34 R. 42W
C SW SE
3300' E WL 660' N SL SE

Total Depth. 4660'
Comm. 10-9-56 Comp. 10-23-56
Shot or Treated.
Contractor. Nye & Snell Drlg. Co.
Issued. 4-20-57

County Morton
KANSAS



Elevation. 3510' GL

Production. 111 BOPE

CASING:

8 5/8" 1505' w/800 sx cem.
5 1/2" 4616' w/400 sx cem.

Figures indicate Bottom of Formations.

sand-shale	266
red ved-shale	735
shale-lime	1510
red bed-shale	1616
shale	2361
lime-shale	3330
lime-shale-sand	3465
lime-shale	4660
Total Depth	

TOPS:

U. Morrow sand	4176-4219
*G sand	4552
Keyes sand	4594

TOPS: Scout

Wabaunsee	2687
Topeka	2886
Lansing	3143
Marmaton	3870
Cherokee	3957
Morrow	4166
Mississippi	4602

PERFORATIONS:

4553-4565'

Fractured w/5000 gals. crude
oil w/1/2# of sand PG on 10-27-56.