

PANHANDLE EASTERN PIPE LINE COMPANY

Riley "C" No. 01  
C SW  
Section 26-34S-42W  
Morton County, Kansas

Formation Tops

Marmaton	3844'
Cherokee	3938'
Atokan	4103'
Morrowan Shale	4174'
"G" Ss	4478'
Keyes Ss	4553'
Mississippian	4593'
Total Depth	4620'

Completion Information

Spud date June 7, 1956  
Set 1497' of 8 5/8" casing with 800 sacks cement  
Set 4575' of 5 1/2" casing with 800 sacks cement  
Cleaned out 4544'  
Perforated 24 holes 4529-33' - Trace oil  
Perforated 60 holes 4523 - 33'  
Treated with 1000 gals 15% acid. Hole filled with  
1500' oil and 500' acid water.  
Perforated 72 holes 4502-4516'. Temporary Jel  
Block.  
Perforated 24 holes 4529-33'  
Treated with 2000 gals 15% acid  
Frac with 5000 gals and 5000 lbs sand  
Treated with 2500 gals 7 1/2% acid

Completion Test: August 16, 1956. State Pump  
Test 42 BOPD - Morrowan "G"  
Ss 4502-16'; 4523-33' Dually  
completed with Greenwood reservoir.