

PANHANDLE EASTERN PIPE LINE COMPANY

Westerfield 01
C SW SE
Section 35-34S-42W
Morton County, Kansas

Formation Tops

Marmaton	3870'
Cherokee	3957'
Atokan	4101'
Morrowan Shale	4166'
"A" Ss.	4176'
"C" Ss.	4219'
"G" Ss.	4552'
Keyes Ss.	4594'
Mississippian	4602'
Total Depth	4660'

Completion Information

Spud October 9, 1956.
Set 1505' of 8 5/8" casing with 800 sacks cement.
Set 4616' of 5 1/2" casing with 400 sacks cement.
Cleaned out to 4587'.
Perforated 48 holes 4553-65'; bailed 15 GOPH.
Fractured with 5000 gallons with 2500# sand.
Swabbed 7 1/2 BOPH.
Ran 2 3/8" tubing and rods at 4553'.

Completion Test: November 28, 1956.
State Test Pumped 111 BOPD
from the Morrowan "G" Ss.
4553-65'.