

State Ks Field GREENWOOD
 Company C.S.O. County MORTON
 Farm KIBBE No. 1
 Sec. 1 Twp. 34 S Range 42 W
 Spot 1250' N & W of center
 Contractor HOLM PA
 Remarks REPL. U.P. & Col. Fuel int. 3300
 Comm. 9-21-58 Comp. 10-5-58
 Elev. DF 3399 GL 3393 KB 3400 TD 3300 PB
 Pay TOP 2962 - 3104



12/20 test
 I.P. 23.7 # Press. 352.7 #

Casing Record: 13 3/8 7"
 20" 10 3/4 5 1/2" 3297/400
 16" 8 5/8 600/350

loc.	Sample	Log
SEP 24 spud, csg, WOC		Top <u>+461 2938</u>
OCT 1 TTD, 3300,		<u>+192</u>
logs, csg, WOCT		<u>Loss 32007</u>
OCT 8 MICT RU		
swbd hole dry		
C.O. 3265		
P 24/3252-58 N.S.		
trtd w/ A/1000 (15%)		
swbd, 150 gal xwtr PH		
1000' xwtr in hole,		
no gas, scum of oil,		
sg perf w/ 150		
pull tbg. prep		
to perf.		
OCT 15 P 40/3212-22, NS, A/1000 (10%)		
flo 350 gw/1' 5G. set ply @ 3120		
P 160/3064-3104 g. 2,830 mcf (dry)		
A/1000 (15%) 4' BD g. 18,900 mcf.		
+ sand mist. 16' BD g. 17,100 mcf		
P 32/2994-3002 P 28/2976-83		

P 24/2962-68 A/200 (7½) +
2000 (15%) swbd. 16' BD
g. 20, 100 mcf ~~SI~~

¢ 72' 20 tst 23,700 mcf
72 HSIP 352.7#
pay Top 2962 - ~~3002~~ 3104 ?

AMARILLO TOPS

3393 GL

Topeka 2936 (#467) @ 23,700 MCF