

CO well

5

State KANSAS County MORTON
 Company CITIES SERVICE GAS DEVELOPMENT
 Farm BROADSHAW "B" Well No. #1
 Sec. 23 Twp. 34S Range 42 W
 Blk. 42 Survey W
 fr N fr E fr S fr W
 of 330 S & 330 W of C.
 Contractor HOLM DALY

Remarks
 Comm. 10-10-55 Comp. 11/16/55
 3481 DF 3498 Elev. 3498 T. D. 3240 P. B. 3150
 Pay 2928-36 - 2952-76 - 2980-95
3114-22

I. P. 14, 400 R. P.
 Casing Record: 13 3/8 7
 20 10 3/4 5 1/2 3233/3000
 16 8 5/8 600/200

		Tops	log by Co.
	TTD 605' raw 8 7/8"		
	@ 600 W 200		TOP 2928
	WOC		Long 3184
<u>OCT 19 1955</u>	Ø 3025		
<u>OCT 19 1955</u>	RTD 3240'		
	raw log		
	raw 5 1/2" to 3233'		
	W 300.000		
	WOC		
<u>OCT 25 1955</u>	MILT ✓		
	pf. 25/3181-96 - NS		
	A/2000 15% flush 3200/H ₂ O sub		
	down - sho gas + 40 gal H ₂ O/hr.		
	WEST Wty		
<u>NOV 2 1955</u>	set plug @ 3150 pf 40/3114-22		
	A/1000 15% H ₂ O/2200, subbed		
	4 hrs g 2,120 mft 3 gts H ₂ O ph.		
	9 hrs g 1,750 mft + 1 1/2 gts H ₂ O ph		

18 hrs. 1,340 mft + 1 1/2 pts ph.
20 hrs 1,340 mft + 1 1/2 pts H₂O ph.
set Baker plug @ 3100 Pf 210/3038-80
A/5000 H₂O/3125 sanded dry -
1 1/2 hr g 6,400 muf. 24 hrs BD
g 6,400 muf + mud set Baker
plug @ 3020 Pf .75/2995-80 120/2926-52
40/2936-28 A/5000 H₂O/3000
sanded - g 1 1/2 hrs. 7,830 muf.
14 hrs Blew 6,400 muf w bu. mud.
A/2000 7.5% H₂O/3000 ϕ plug
@ 3020 + 3100 sanded down.
12 hr BD g 7,150 muf.

SI,

NOV 9 1955 | SI - 72 hrs; blew - 12 hrs To dry

5 min g - 20,700 muf 10" gag. 17,100
15 " 14,400 20" 13,700

SI - ✓ SIP 427 #

Nov 16, 1955: 72/20 14,400 muf
SIP 427 #

ϕ