

Field _____
State Kansas County Morton
Company Colo. Oil & Gas Co.
Farm Central Life Well No. 1-32
Sec. 32 Twp. 34S Range 42W
fr N _____ fr E _____ fr S _____ fr W _____
of C NW 1/4
Contractor Holm Drlg.
Remarks _____
Comm. 10-8-55 Comp. 12-14-55
Elev. 3532 GL 3531⁰⁵ T. D. 4730 P. B. 3050
Pay 2876-80 - 2882-84 2890-96 - 2915-20
2957-68 - 3024-28
I. P. 5,200 MCF S/L 405#
Casing Record: 13 3/8 _____ 7 3887/375
20 _____ 10 3/4 _____ 5 1/2 _____
16 9 5/8 1304/600

		Tops
		<u>Ramp top</u>
		<u>Wab 2640</u>
	<u>Ø 3367</u>	<u>Elmont 2870</u>
		<u>TOP 2934</u>
<u>OCT 1 9 1955</u>		
<u>OCT 2 6 1955</u>	<u>DST #1 3357-97 opn</u>	<u>LeCont 3065</u>
	<u>65" gts in 6" 10" g 175 mcf.</u>	<u>Sony 3272</u>
	<u>25" g 186 mcf. 35" g 196 mcf.</u>	<u>Mann 3682</u>
	<u>rec 70' gcm FP 100-120</u>	<u>Atoka 3894</u>
	<u>BH 600/30</u>	<u>Mor 4217</u>
	<u>DST #2 3551-3608 opn</u>	
	<u>75" rec 990' mudlog SW</u>	
	<u>FP 70-440 BH 680/30</u>	
	<u>DST #3 3643-3725 opn</u>	
	<u>1 hr rec 204 slig g cm FP 150</u>	
	<u>BH 630/30</u>	
	<u>DST #4 3742-3804 opn</u>	
	<u>2 hrs wk blo died in 20" by passed</u>	
	<u>wk blo died 10" rec 145'm</u>	
	<u>FP 80-150 BH 590/30</u>	
	<u>TTO 3975 rpy to DST</u>	
	<u>DST 3896-3975</u>	

NOV 2 1955 DST 3896-3975 open 2 hrs.
 sh. bls. 45" + descr. Rec 1400'
 muddy LW FP 450-780 BHSIP 840/30
 DST 3995-4270 open 2 hrs. fr. bls
 grad dec. to wk. Rec 120' radi
 g & m FP 45-120 BH 580/30
 T+D 4450 Num sch.
 RTD 4730 Num sch.
 DST 4589-4601 (ap) open 1 hr. Rec 45'
 g & salty mud w rainbow sh. and
 1560' grady LW. FP 180-750
 BH 960/30 set 7" @ 3887/375
 WOC

NOV 9 1955 WOC7

NOV 16 1955 RUT CO to ?
 prep tr. pt.

NOV 22 1955

CO pf 36/3763-22 Main 3834
 sub 7g wph sh. gas - Ck 3924
 A/2500 - sub 200g swph - Atrdn 4064
 set @ 3738 sq w 250 sq. Mar 4194
 pf - 32/3638-46 - A/2000 Keya 4598
 sub 750 g wph set @ Mar 4659
 3582 sq 250 sq. pf 20/3363-68 A/1000.
 g 298 muf + 150 g wph - Tudy

NOV 30 1955

set set @ 3299 sq 250 muf
 pf 24/302K-80 A/1500 g 60 muf
 + AW set set @ 3050 sq 250 sq
 pf 56/302K-38 A/3000 g 2,400
 muf + 150 g wph set - 1,700 muf
 + 38g wph set plug @ 2990 pf 64/2952-68
 g 2,720 muf. A 3500 g 2,300 muf
 + 25g wph.

DEC 7

g plug @ 2990 g 1,740 muf + 40g wph
 set plug @ 2935 pf 2915-20 24/2890-96
 8/2882-842 A/3500 g 2,328 + 48g wph

Log top
 WOC 2638
 Elmont 2867
 Top 2948
 LComp 3068
 Long 3351

Field

State

County

Company

Farm

Well No.

Sec. 32 Twp. 34 Range 42 W

Blk. 34 Survey

fr N fr E fr S fr W

Contractor

Remarks

Comm. Centinal Life 1-37 Comp.

Elev. T. D. P. B.

Pay

I. P. R. P.

Casing Record: 13 3/8 7

20 10 3/4 5 1/2

16 8 5/8

plug @ 2935 Tops

2264 + 15 guph set plug

@ 2675 pf 16/2652-56 H/1100

g 45 guph prep to sg.

DEC 14 1955 Lot 2675 plug Lot 3050 g

2570 Mef + 15 guph has 1 1/4" T to 3048

Prod 2 3024-28 - 2952-68 2915-20 2890-96

2882-84 2876-80

72/20 g 5 200 MCF WET

SIP 405#