
5

Field

State Kansas County Morton
 Company PEPL
 Farm Land Bank Well No. 2-34
 Sec. 34 Twp. 34S Range 42 W
1519' fr W 1320' fr L fr S fr W
 of Sec. 200' E of CNW
 Contractor Garvey Drlg. Co.

Remarks

Comm. 10-21-55 Comp. 12-21-55
 Elev. 3538 DF 3532 P.D. 3698 P. B. 3415
 Pay Lower Zone - 3343-61 - 3365-84 prod PK @
3425 - Upper Zone 2874 - 2909 - 2929 - 37 - 2957 - 71
2993-99 - 3075-97 Dual Completion RP 480
P. Uppelberg 5,119 R.P.
Lower Zone 9,008 RP 615
 Casing Record: 13 3/8
 20 10 3/4 5 1/2 3698/375
 16 8 5/8 593/350

Date	Well No.	Notes	Depth
10-26-55	Ø 2400	Tops	
		log tops	
		Wab	2631
NOV 2 1955		RTD 3700'	Top 2829
		run log	Lang 3066
		set 5 1/2	3698/325
		WOC	
NOV 9 1955		RCT CO to 3695	
		pf 16/3656-60	20/3647-5
NOV 16 1955		16/3638-42	A/1000
		run skt gas set pty @ 3615	
		pf 48/3552-64	120/3529-34
		24/3520-26	A/1000 g 1, 846 mg
		w 700-800 g wph	pk @ 3505 mg
		w 150 sup CO to ?	up pf 24/3520
-26		20/3529-34	A/1000 g 800 mg
		+ 150 g wph set set @ 3496 mg	
		w 200 sup	sub well dry pt
		56/3448-62	28/3426-33 no skt
		prep to Acidize	

NOV 22 1955

A/1000 g 72 mcf + AW set
 pl at 3415 pf 16/3380-84 .40/3365-25
 24/3355-6 32/3343-51 g 200 mcf
 8 hr BD 442 mcf - A/1000 g
 16,450 mcf. A/1000 A/2000 7.5%
 9 hr BD 12,675 mcf. alt play @
 325 pf 24/3091-97 36/3075-79
 24/2993-99 56/2957-71 32/2929-37
 24/2903-09 52/2874-87 g 1,196 mcf
 test. A/3000 1 hr BD g 17,095 mcf.
 4 hr BD g 16,490 mcf. in 14 hrs 5/
 press 431.1# A/3000 A/2000 7.5%
 4 hr BD g 18,895 mcf. ~~running test~~
 for ~~well~~ completion:

NOV 30 1955

above play 3415 WOT

DEC 7 1955

State Reliability

5,119 mcf upper Lansing
 RP 430.1#

~~well is not dually completed~~

~~has no tubing~~

DEC 14 1955

well is dually completed.

DEC 21 1955

STATE TEST #

Lower Lang. 9,808 mcf Act of flr.
BHP. 615.2#

(3343-3384)

have prod pk 3325

Ⓞ