


\*\*\* off-foot  
(if gas)

State KS Field TALOGA  
Company PEPL County MARTON  
Farm HALL No. 0-1  
Sec. 35 Twp. 34 Range 42  
Spot SW NE  
Contractor GARVEY  
Remarks M.I.S.S.



Comm. 2-28-58 Comp. 5-21-58  
Elev. 3511 DF 3505 GL 3505 KB 4720 PB 4670  
Pay 4644-66 33 GOR 328.1

purp I.P. 72.5 BOPD Press.  
Casing Record: 13 3/8 7"  
20" 10 3/4 5 1/2" 4703/208  
16" 8 5/8 1408/800

| Loc.                                                   | Sample | Log              |
|--------------------------------------------------------|--------|------------------|
| FEB 19                                                 |        | Lab- 2705        |
| FEB 26                                                 |        | Top 2907         |
| MAR 5 <del>spud, csg</del>                             |        | CSD/AN 3162      |
| <del>φ 2080</del>                                      |        | IAN 3346         |
| MAR 12 <del>φ 2962</del>                               |        | Clear 4001       |
| MAR 19 <u>E 4275-4306</u>                              |        | Mo. sh 4222      |
| Rec. 26 1/2                                            |        | "C" ss 4281-     |
| 5' sh ; 2 1/2' ss fi-cse                               |        | "F" ss 4303      |
| odor                                                   |        | 4486             |
| <u>DST 4282-4306</u> <sup>up. for.</sup> <sub>ss</sub> |        | "G" ss 4636-     |
| op 27", gts 1"                                         |        | 67               |
| 2,828 mcf - 2"                                         |        | Keyes 4678-      |
| 6,352 " - 27"                                          |        | 4707             |
| Rec 65' gcm                                            |        | <u>Miss 4709</u> |
| FP 1060-1060                                           |        |                  |
| BHP 1140/20"                                           |        |                  |
| DST 4488-4530 <sup>op. 1"</sup> Rec 20' 56cm           |        |                  |
| FP 0-0, BHP 260/20"                                    |        |                  |
| E 4619-54 Rec 35' - 22' ss ; 13' sh                    |        |                  |
| E 4654-45 1/2 Rec. 11 1/2' ss                          |        |                  |
| E 4665 1/2 - 88 Rec. 22 1/2' ;                         |        |                  |
| 10 1/2' sh ; 12' ss                                    |        |                  |
| <del>44690</del>                                       |        |                  |

MAR 26 RTD 4720, 5; ~~5 1/2~~", RUCT

CO. 4670

P/8 4654 - 56 Sured 3-4 gals

4656 - 66, ~~prop pf~~

APR 1 P/40 4656 - 66

32 4644 - 52, Sured 6 gals oil +

2 gals wtr/hr, Ac 500 ma

Sured 15 gals oil/hr.

frac 5000 gal dies x 2500 sd

Sured 2d & Sured 20 BNOPH, ~~thg~~

APR 92 1/2" ~~thg~~ 4651 ~~thg~~

APR 16

APR 23

APR 30

MAY 7

MAY 14

MAY 21

State 1st

prop + fluid 72.49 BOPD  
GOR 328:1

### AMARILLO TOPS

3505 GL

Morrow 4222 (-717)

"L" 4280 (-775) 22/22, tst'd 6,400 MCF

~~53~~ Keyes 4635 (-1136) 18/31 b, c 72.5 BOPD

Keyes 4684 (-1179) 20/23

Chester 4707 (-1202)

263