


XXX

State Kans Field Taloga
 Company PEPL County Montau
 Farm western field No. 0-9
 Sec. 35 Twp. 3F Range 42

Spot CNE, SE

Contractor Mye & Snell

Remarks miss



Comm. 11-10-56 Comp. 1-23-57

Elev. DF 3574 GL 3517 KB TD 5024 PB

Pay Dual camp - 4576-92 PK @ 4546

4515-22
12580 PD upzone
 I.P. 193 " lower " Press.

Casing Record: 13 3/8 7"

20" 10 3/4 5 1/2" 5020/200

16" 8 5/8 1872/250

	Sample	Log
~~Ø 1298~~		wob 2791
~~TTD 1981~~		TOP 3002
~~WOL~~		CSOLan 3264
NOV 21		Lan 3976
~~Ø 3609~~		char 4204
NOV 27		Mor 4499
Ø 4240-86 rec 46'		sd 4512-22
46' Ls & sh		sd 4573-96
DST 4477-5533 op/lh.		" 4910-32
rec 400' clean oil + 80' ocm		" 4954-73
FP 45-160, BHP 1130/20		" 4994-5028
Ø 4533-80 rec 39'		
20' sd,		
19' sh.		
DEC 5		
Ø 4606-53 rec 10'		
2' sh		
2' Ls		
6' sh		
Ø 37 lost		
RTD 5024 ran log PK		
DST 4898-5004 op/lh. rec 440' sh. 9cm		
+100' filtrate FP 70-290, BHP 1000/20		
PK @ 5020/200 WOL		

DEC 12 RUC TCO Preptolog

DEC 19

ran 6/R pf 9/4994-95.5 swab SW
ret @ 4975 sg/200, pf 9/4963.5-65
swab 400gsw PH, pl 4948 sg/200
pf 9/4916-17.5 bail 60gsw PH ret 4870
sg/100 ~~w oc~~

JAN 8

co pf 64/4576-92 swab f/10
100 BO in 1 1/2 hrs. set pl @ 4530 pf 48/
4514-22 swab 4-5 BOPH. fn/5000
sd/2500 swab 18 BOPH for 2 hrs.
~~0 pl to T.D. - 4523 T + R - 4523 comp.~~
~~pk 4546. - 4523~~
Ran T + pk @ 4546. P.O.P

JAN 9 ✓

JAN 16 ✓

JAN 23

State Pat { Rump 125 BOPD upper zone
" 193 " lower zone

AMARILLO TOPS

3525 KB

Topeka 3000 (+525)

Heebner 3342 (+183)

Lansing 3474 (+51)

Morrow 4500 (-975)

"S-1" Sd 4514 (-989) T 10', por 10', 125 BOPD

"L" sd 4574 (-1049) T 22', por 22', 193 BOPD

"S-3" Sd 4910 (-1385) T 24', por 10', tst'd XW

Keyes Sd 4958 (-1433) T 58', por 44' b, XW

Miss 5030 (-1505)