

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


20-34-43 W

Company. J. M. HUBER CORPORATION
Farm. Interstate or No. 3
Block "A"

SEC. 20 T. 34 R. 43W
C NW SE

Total Depth. 4260
Comm. 9-16-55 Comp. 9-27-55
Shot or Treated.
Contractor. J. M. Huber Corporation
Issued. 11-26-55

County Morton
KANSAS



Elevation. 3484 DF

Production. 243 BOPD

CASING:

13" 80'
8" 1100'
5" 4219'

Figures indicate Bottom of Formations.

sand & clay	85
sand & red bed	222
red bed & shells	550
red bed, shells & gyp	765
sand	928
gyp, lime, shells & red bed	1090
anhydrite	1120
anhydrite & lime	1400
red bed & shells	1915
shale & shells	2269
lime & shale	3867
lime	4148
Core #1-sandy shale, sand & shale	4188
lime & shale	4260
Total Depth	

TOPS:	SAMPLE	ELEC. LOG
Topeka		2670
Lansing	2898	2902
Morrow shale	4057	4052
First Sand	4105	4107
Purdy sand	4151	4151
Sand	4232	4232

DST #1: 4100-20, open 1 hr. gas to surf. 13 min. gauged 60 MCF, rec. 120' VSOCM, 450' SO&GCSW, IFP 90#, FFP 240#, BHP 975#/20 min.

DST #2: 4147-88: open 55 min. gas to surf. 5 min. gauge 375 MCF, flow oil 47 min. rec. 990' clean oil, 90' VSSW, IFP 240#, FFP 495#, BHP 1125#/20 min.

Core #1: 4148-4188, rec. 37.5'