

KANSAS

State Geological Survey 12/21/80
20A BRANCH 43 W

WELL COMPLETION REPORT AND DRILLER'S LOG

API No. 15 — 129 — 20,454
County Number

S. 20 T. 34S R. 43 ^{EX} W
Loc. 1650' FSL & 1250' FEL

County Morton

640 Acres
N

Operator
Anadarko Production Company

Address
P. O. Box 351, Liberal, Kansas 67901

Well No. 3 Lease Name INTERSTATE "F"

Footage Location
1650 feet from ~~XOX~~ (S) line 1250 feet from (E) ~~WFO~~ line

Principal Contractor KTM Drilling Company Geologist John Jacobson

Spud Date 12/5/80 Date Completed 12/21/80 Total Depth 1330' P.B.T.D. 1310'

Directional Deviation not applicable Gas Purchaser Panhandle Eastern Pipeline Co.

RELEASED

Date: DEC 1 1980

FROM CONFIDENTIAL

Locate well correctly
Elev.: Gr. 3476'

DF 3480' KB 3481'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	378	Common	350	3% CaCl
Production	7-7/8"	4-1/2"	10.5#	1324'	Lite-wate SS Pozmix	350 150	.5% tic .5% tic

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	.46	1179-1210' O.A.

TUBING RECORD

Size	Setting depth	Packer set at
2-3/8"	1148'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
A/1300 gal 15% Spearhead + 75 BS	1179-1210' O.A.

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)
SI for Pipeline Conn	Flowing
RATE OF PRODUCTION PER 24 HOURS	Oil --- bbls. Gas 164 MCF Water --- bbls. Gas-oil ratio --- CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval(s)
to be sold	1179-1210' O.A.

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

10-24-1980

	Date Received
Date December 22, 1980	
Title Paul Campbell, Division Production Manager	
Signature <i>Paul Campbell</i>	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

DEPTH	NAME	BOTTOM	TOP	FORMATION DESCRIPTION, CONTENTS, ETC.
158'			0'	Sand & shale
383'			158'	Sand Red Clay
478'			383'	Sand & Clay
594'			478'	Sand Clay
655'			594'	Red Clay & Red shale
765'			655'	Anhydrite & Redbed
1095'			765'	Glorietta
1265'			1095'	Red shale & Anhydrite
1330'			1265'	Red shale sand

	Operator Anadarko Production Company
	Well No. 3
	Lease Name INTERSTATE "F"
	GAS
SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.	
WELL LOG	
S 20 T 34S R 43 B W	

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: