

KANSAS

12/18/80  
20-34-43W

**WELL COMPLETION REPORT AND DRILLER'S LOG**

S. 20 T. 34S R. 43 W

API No. 15 — 129 — 20,455  
County Number

State Geol. & WL

Loc. Geol. & WL  
WICHITA, Morton  
County, Kansas  
640 Acres  
N

Operator  
Anadarko Production Company

Address  
P. O. Box 351, Liberal, Kansas 67901

Well No. 4 Lease Name INTERSTATE "F"

Footage Location  
1330 feet from (N) line 1330 feet from (W) line

Principal Contractor KTM Drilling Company Geologist John Jacobson

Spud Date 11/20/80 Date Completed 12/14/80 Total Depth 1298' P.B.T.D. 1282'

Directional Deviation not applicable Oil and/or Gas Purchaser Panhandle Eastern Pipeline Co.

**RELEASED**  
DEC 1 1982  
FROM CONFIDENTIAL

Locate well correctly  
Elev.: Gr. 3474'  
DF 3478' KB 3479'

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	370	Common	350	3% CaCl
Production	7-7/8"	4-1/2"	10.5#	1292	Lite-wate SS Pozmix	350 150	.5% tic .5% tic

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	.46	1206-36 O.A.

**TUBING RECORD**

Size	Setting depth	Packer set at
2-1/16"	1206'	

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated
A/250 gals 15% Spearhead + 10 BS	1234-36'
A/1300 gal 15% Spearhead + 75 BS	1224-36'; 1206-24'

**INITIAL PRODUCTION**

Date of first production SI for Pipeline	Producing method (flowing, pumping, gas lift, etc.) flowing
RATE OF PRODUCTION PER 24 HOURS	Oil --- bbls. Gas 240 MCF Water --- bbls. Gas-oil ratio --- CFPB
Disposition of gas (vented, used on lease or sold) To be sold	Producing interval (s) 1206-36' O.A. (Redcave)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator  
Anadarko Production Company

Well No. 4  
Lease Name INTERSTATE "P"

GAS

S 20 T 34S R 43 W

**WELL LOG**  
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

FORMATION DESCRIPTION, CONTENTS, ETC.

DEPTH	NAME	BOTTOM	TOP	FORMATION DESCRIPTION, CONTENTS, ETC.
236'		236'	0'	Sand Clay & Red Shale
375'		375'	236'	Shale & Anhydrite
629'		629'	375'	Red Shale
770'		770'	629'	Shale & Anhydrite
1105'		1105'	770'	Sand & Shale
1250'		1250'	1105'	Shale & Anhydrite
1285'		1285'	1250'	Anhydrite & Red Shale

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

*Paul Campbell*  
Signature

Paul Campbell, Division Production Manager  
Title

December 16, 1980  
Date

1285-43-20