

KANSAS

WELL COMPLETION REPORT AND *State Geological Survey*
DRILLER'S LOG

WICHITA BRANCH

API No. 15 — 129 — 20,456
County Number

Operator

Anadarko Production Company

Address

P. O. Box 351, Liberal, Kansas 67901

Well No.

5

Lease Name

INTERSTATE "F"

Footage Location

1980 feet from ~~XX~~ (S) line 1320 feet from ~~XX~~ (W) line

Principal Contractor

KTM Drilling Company

Geologist

Mr. Jim Druyff

Spud Date

12/10/80

Date Completed

7/31/81

Total Depth

1305'

P.B.T.D.

1295'

Directional Deviation

not applicable

Oil and/or Gas Purchaser


DRY HOLE

S. 20 T. 34S R. 43 ~~XX~~ W

Loc. C N/2 SW/4

County Morton

640 Acres



Locate well correctly

Elev.: Gr. 3482'

DF 3486' KB 3487'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20#	376'	Common	350	3% CaCl
Production	7-7/8"	4-1/2"	10.5#	1303'	Lite-wate SS Pozmix	350 150	.5% D-31 5% D-31

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	.46 jet	1207-15'; 1221-29'
Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
A/1000 gal 15% Spearhead + 40 BS	1207-15' & 1221-29'

RELEASED

INITIAL PRODUCTION

Date: JUN 30 1983

FROM CONFIDENTIAL

Date of first production

DRY HOLE

Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION
PER 24 HOURS

Oil

bbls.

Gas

MCF

Water

Gas-oil ratio

bbls.

CFPB

Disposition of gas (vented, used on lease or sold)

Producing interval(s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator
Anadarko Production Company

Well No. 5
Lease Name INTERSTATE "F"

5 20 T 34S R 43W E

WELL LOG
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

NAME DEPTH

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM
Surface Sand, Clay	0'	120'
Red shale, Rocks & Redbed	120'	319'
Red shale & Anhydrite	319'	383'
Redbed, Red shale & Anhydrite	383'	670'
Red shale & Anhydrite	670'	970'
Anhydrite, Red shale & Clay	970'	1195'
Anhydrite & Red shale	1195'	1300'
Sand, Silt & Anhydrite	1300'	1305'

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received
Signature
Paul Campbell, Division Operations Manager

Title
November 12, 1981
Date

11-34-43W



KTM DRILLING, INC.

ARNOLD WINTER -:- PH. (405) 338-3144 -:- GUYMON, OKLAHOMA

BUSINESS OFFICE
BOX-181 -- (806) 733-2284
GRUVER, TEXAS 79040
Box 1285, Guymon
Oklahoma 77040

December 16, 1980

STANDARD PRODUCTION COMPANY
P.O. Box 351
Liberal, Kansas 67881

ATTN: PAUL BATHIN

Drillers Log For:

0' - 120'
120' - 340'
340' - 383'
383' - 670'
670' - 970'
970' - 1195'
1195' - 1300'

Interstate "F" #5

Surface sand clay
Red shale, rocks, & red bed
Red shale & anhdy
Red bed, red shale & anhdy
Red shale & anhdy
Anhdy, red shale & clay
Anhdy & red shale

KTM DRILLING, INC.

Arnold Winter
ARNOLD WINTER

STATE OF OKLAHOMA
COUNTY OF TEXAS

Subscribed and sworn to before me this 16th day of December, 1980/

Daniel V. Norris
NOTARY PUBLIC

My commission expires: 12-17-83