

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


20-34-43W

Company- H. M. HUBER CORPORATION
Farm- Interstate Block No. 5
"A"

SEC. 20 T. 34 R. 43W
C SE NW

Total Depth. 4552'
Comm. 10-17-55 Ccmp. 10-31-55
Shot or Treated.
Contractor.
Issued. 3-30-57

County Morton
KANSAS



Elevation. 3503'

Production. 140 BOPD

Figures indicate Bottom of Formations.

CASING:
13" 075'
8" 01193'
5" 04300'

sand & gravel	55
redbed	75
redbed & shells	150
redbed	655
redbed, shells & lime	
stringers	1070
redbed & lime	
stringers	1160
Anhydrite	1193
redbed & shells	1488
lime & shale	3098
lime & waxy shale	3152
lime & shale	3740
lime & chert	3828
lime & shale	3898
lime & shale & chert	3974
lime & chert	3986
lime & shale	4171
Core (sand & shale)	4210
lime & shale	4368
lime	4440
Core (shaly sand & shale)	4470
shale & lime	4500
lime & shale	4526
lime	4552
Total Depth	

TOPS	SAMPLE	ELECTRIC
Topeka	2693	2693
Lansing	2920	2922
Morrow Shale	4072	4072
First Morrow Sand	4134	4135
	(poorly developed)	
Purdy Sand	4169	4170
Second Morrow Sand	4260	4260
	(poorly developed)	
"G" Sand	4450	4450
Keyes Sand	4475	4475