

State Geological Survey KANSAS DRILLERS LOG WICHITA, KANSAS

21-34-43W

S. 21 T. 34S R. 43 E
W
Loc. 1320' FSL & 50' FWL
County Morton

API No. 15 — 129 — 20,213
County Number

Operator
Anadarko Production Company

Address
P. O. Box 351, Liberal, Kansas 67901


Well No. 79 Lease Name Interstate Unit

Footage Location
1320 feet from (N) (S) line 50 feet from (E) (W) line

Principal Contractor DaMac Drilling Co. Geologist Bob Posey

Spud Date 7-27-75 Total Depth 4210' P.B.T.D.

Date Completed 8-7-75 Oil Purchaser



Locate well correctly
Elev.: Gr. 3486.6'
DF KB

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Conductor	30"	20"	48#	75'	Common	200	
Surface	12-1/4"	8-5/8"	24#	1142'	Pozmix Common	400 200	4% gel 2% CC 2% CC
Production	7-7/8"	5-1/2"	15.5#	4205'	Pozmix	100	5% CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2 SPF		4135'-40'
			2 SPF		4123-29'
			2 SPF		4111-17'

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Squeezed w/100 sacks Common.	4135-40'
Acidized w/2000 gallons 7-1/2" NE + 50 ball sealers. Fraced	4123-29' & 4111-17'
w/15,000 gallons gelled lease crude + 15,000# 10-20 sand.	

INITIAL PRODUCTION

Date of first production 9-19-75 Producing method (flowing, pumping, gas lift, etc.) Pumping

RATE OF PRODUCTION PER 24 HOURS Oil 282 bbls. Gas MCF 1285 bbls. Water Gas-oil ratio CFPB

Disposition of gas (vented, used on lease or sold) Will be sold Producing interval(s) 4111-4154' OA

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Anadarko Production Company

Well No.

79

Lease Name

Interstate Unit

Oil

S 21 T 34S R 43 EC
W


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface Clay-Sand-Redbed	75	390		
Redbed-Anhy	390	697		
Anhy	697	1037		
Shale-Anhy	1037	1153		
Shale-Lime	1153	2690		
Lime	2690	2880		
Lime-Shale	2880	4107		
Sand	4107	4144		
Sand-Shale	4144	4210		
Total Depth		4210		
Core #1 4107-4144', REC 37' sand.				
Core #2 4144-4160', REC 13.5' sand, 2.5' shale.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.



Stanley Shoemaker

Signature

Division Office Supervisor

Title

September 30, 1975

Date

51-34-130