

KANSAS DRILLERS LOG

State Geological Survey
WICHITA BRANCH


MAR 17 1977

21-34-43W

S. 21 T. 34S R. 43 E W

Loc. 1420' FNL & 1320 FWL

County Morton

640 Acres
N

Locate well correctly

Elev.: Gr. 3476.4'

DF _____ KB _____

API No. 15 — 129 — 20,258
County Number

Operator

ANADARKO PRODUCTION COMPANY

Address

P. O. BOX 351, LIBERAL, KANSAS 67901

Well No.

82

Lease Name

INTERSTATE UNIT

Footage Location

1420 feet from (N) (S) line

1320 feet from (E) (W) line

Principal Contractor

Gabbert-Jones, Inc.

Geologist

None

Spud Date

9:45 AM 7/12/76

Total Depth

4235'

P.B.T.D.

Date Completed

8/9/76

Oil Purchaser

National Co-Op Ref. Ass'n.

CASING RECORD

Report of oil strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	24#	1168'	Pozmix Common	500 200	4% gel, 2% CaCl 3% CaCl
Production	7-7/8"	5-1/2"	15.5# 14#	4234'	S. S. Poz	100	.05% CFR-2 1/4 Tuff Plug

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4		4126-4138 OA
TUBING RECORD					
Size	Setting depth	Packer set at			
2-7/8"	4204'				


ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Filled hole w/100 gal. acetic 10% + 400 gals 2% KCL wtr to perf.	4126-4138 OA
loaded w/2% KCL wtr, A/100 gals acetic 10% acid.	

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
8/3/76		Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	388 bbls.	MCF	330 bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
			4126-4136 OA		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas

Operator: ANADARKO PRODUCTION COMPANY		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: OIL	
Well No. 82	Lease Name INTERSTATE UNIT		
S 21 T134SR 43 E W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
Cased	0'	55'	
Redbed	55'	429'	
Redbed-Gyp	429'	905'	
Redbed-Anhy	905'	1168'	
Anhy-Redbed	1168'	1560'	
Redbed	1560'	1882'	
Redbed-Shale	1882'	2064'	
Shale-Lime	2064'	2285'	
Lime-Shale	2285'	4235'	
TOTAL DEPTH		4235'	
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 Signature Stanley R. Shoemaker, Div. Ofc. Mgr. Title October 26, 1976 Date		

91-30-030