

State Geological Survey

WICHITA BRANCH
KANSAS DRILLERS LOGAPI No. 15 — 129 — 20,341
County Number

Operator

ANADARKO PRODUCTION COMPANY

Address

P. O. BOX 351, LIBERAL, KANSAS 67901

Well No.

84

Lease Name

INTERSTATE UNIT

Footage Location

250 feet from (N) (S) line

160 feet from (E) (W) line

Principal Contractor

Gabbert-Jones, Inc.

Geologist

Spud Date

12/2/77

Total Depth

P.B.T.D.

Date Completed

2/17/78


Oil Purchaser

National Co-Op Refinery

S. 28 T. 34S R. 43 X
W

Loc. 250' FNL & 160' FWL

County Morton

640 Acres
N

Locate well correctly

Elev.: Gr. 3471'

DF KB

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	24#	1166'	Lite Wate Common	500 200	4%, 2% cc 2% cc
Production	7-7/8"	5-1/2"	14#	4176'	S.S. Pozmix	150	.05% CFR-2, 1/4#/ Tuff Fiber

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2		4084-92'
			2		4102-08'

TUBING RECORD

Size	Setting depth	Packer set at			
2-3/8"	4010'	4097'	2		4102-08'


ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Loaded w/100 gals 10% Acetic Acid + 400 gals 2% KCL.	4084-92'
Spotted 500 gals 7-1/2% acid @ 4110'	4102-08'

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
2/2/78		Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	51.3 bbls.	MCF	1663 bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
			4084-4108'		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator ANADARKO PRODUCTION COMPANY		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: OIL	
Well No. 84	Lease Name INTERSTATE UNIT		
S <u>28</u> T <u>34S</u> R <u>43</u> ^E _W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	
Cased Hole	0'	66'	
Surface Clay-Sand-Redbed	66'	386'	
Sand-Redbed	386'	680'	
Anhy-Sand-Redbed	680'	1113'	
Redbed-Anhy	1113'	1168'	
Anhy-Redbed-Sand	1168'	1757'	
Redbed-Anhy	1757'	2035'	
Sand-Shale w/Lime Stks	2035'	2278'	
Lime-Shale	2278'	4180'	
TOTAL DEPTH		4180'	
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 Signature Paul Campbell, Division Production Manager Title February 28, 1978 Date		

98-34-4300