

PANHANDLE EASTERN PIPE LINE COMPANY

Interstate "C" 01
C NE SW
Section 16-34S-43W
Morton County, Kansas

Formation Tops

Marmaton	3740'
Cherokee	3844'
Atokan	4051'
Morrowan Shale	4150'
Interstate Ss.	4198'
Total Depth	4345'

Completion Information

Spud March 13, 1957
Set 1207' of 7" casing with 800 sacks cement
Set 4327' of 4½" casing with 150 sacks cement
Cleaned out to 4283.
Perforated 16 holes from 4230-34.
Perforated 20 holes from 4201-06.
Fractured 3000 gallons kerosene, 1500# sand.

Completion Test: May 22, 1957.
Pumped 256 BOPD from the
Morrowan Interstate Ss.
4201 to 4206 and 4230 to 4234.