

PANHANDLE EASTERN PIPE LINE COMPANY

Interstate "B" 03  
C SE SW  
Section 17-34S-43W  
Morton County, Kansas

Formation Tops

Marmaton	3709'
Cherokee	3815'
Atokan	4010'
Morrowan Shale	4130'
Interstate Ss	4201'
Total Depth	4287'

Completion Information

Spud August 4, 1956  
Set 113' of 13" casing with 200 sacks cement  
Set 1138' of 8 5/8" casing with 750 sacks cement  
Set 4260' of 4 1/2" casing with 400 sacks cement  
Cleaned out to 4234'  
Perforated 40 holes 4203' to 4213'

Completion Test: October 17, 1956 pumped 123 BOPD  
from Morrowan Interstate Ss 4203'  
to 4213'