

PANHANDLE EASTERN PIPE LINE COMPANY

Interstate "C" 05
C NW SW
Section 16-34S-43W
Morton County, Kansas

Formation Tops

Marmaton	3732'
Cherokee	3835'
Atokan	4032'
Morrowan Shale	4130'
Interstate Ss.	4181'
Total Depth	4300'

Completion Information

Spud December 4, 1956.
Set 123' of 10 3/4" casing with 100 sacks cement.
Set 1179' of 7" casing with 750 sacks cement.
Set 4299' of 4½" casing with 200 sacks cement.
Cleaned out to 4259'.
Perforated 80 holes 4194-4214'.

Completion Test: January 17, 1957.
Pumped 481 BOPD from the
Morrowan Interstate Ss.
4194 to 4214'.