

PANHANDLE EASTERN PIPE LINE COMPANY

Interstate 08
C NE NW
Section 21-34S-43W
Morton County, Kansas

Formation Tops

Marmaton	3701'
Cherokee	3803'
Atokan	4001'
Morrowan Shale	4102'
"B" Ss	4118'
Interstate Ss	4151'
Total Depth	4244'

Completion Information

Spud October 16, 1956
Set 113' of 10 3/4" casing with 100 sacks cement
Set 1116' of 7" casing with 750 sacks cement
Set 4241' of 4 1/2" casing with 200 sacks cement
Cleaned out to 4212'
Perforated 100 holes 4153' to 4173'

Completion Test: January 15, 1957 pumped 245 BOPD
from the Morrowan Interstate Ss
4153' to 4173'