

PANHANDLE EASTERN PIPE LINE COMPANY

Interstate 011  
C SW NE  
Section 21-34S-43W  
Morton County, Kansas

Formation Tops

Marmaton	3694'
Cherokee	3796'
Atokan	3996'
Morrowan Shale	4095'
Interstate Ss	4148'
Total Depth	4260'

Completion Information

Spud December 19, 1956  
Set 99' of 10 3/4" casing with 100 sacks cement  
Set 1134' of 7" casing with 750 sacks cement  
Set 4215' of 4 1/2" casing with 200 sacks cement  
Cleaned out to 4178'  
Perforated 8 holes 4154' to 4156'  
Perforated 36 holes 4148' to 4152'

Completion Test: Swabbed 75 gallons salt water  
per hour. Temporarily abandoned.