

PANHANDLE EASTERN PIPE LINE COMPANY

Scott 1-32
C of NW
Section 32-34S-43W
Morton County, Kansas

Formation Tops

Marmaton	3730'
Cherokee	3834'
Atokan	3991'
Morrowan Shale	4119'
A Ss.	4121' —
Total Depth	4180'

Completion Information

Spud May 23, 1956.
Set 1247' of 8 5/8" casing with 597 sacks cement.
Set 4178' of 5½" casing with 800 sacks cement.
Perforated 60 holes 4123-4133'.
Acidized with 500 gallons mud acid.
Fractured with 8000 gallons and 8000# sand.

Completion Test: September 13, 1956.
Calculated WHAOF 13,700 MCF
from Morrowan A Sandstone
4123' to 4133'.